


Cryomodule Concepts & Cryogenics

J.D. Fuerst

SPX Technical Study Group Meeting

27-29JUL10

SPX Layout



RF Building #1 requirements for the RF Components and the RF equipment are:
 600kW AC
 300gpm DI water

- Building 400A - Future SPX Cryogenic Building
 - Will temporarily house SPX RF Test Stand with SC Cavity Enclosure
 - Approximate waveguide lengths:
 25 Feet to S6 Cryo Module
 25 Feet to S8 Cryo Module

RF Building #2 requirements for the RF Components and the RF equipment are:
 500kW AC
 300gpm DI water


Option F

DRAWN BY	DATE	THIS DOCUMENT IS THE PROPERTY OF ARGONNE NATIONAL LABORATORY ADVANCED PHOTON SOURCE SPX - SC RF & Cryogenic Facility	
CHECKED BY	DATE		
DESIGNED BY	DATE		
RESP. ENGR. BY	DATE		
GROUP LEADER	DATE		
APPROVED BY	DATE	Size	Dwg. No.
Release Level	Electronic File Name	Version	Scale
	5-20-2010, t1s		Sheet 1 of 1

JLab 100mA Cryomodule Design

J. Preble, JLab


- RT HOM loads inside vacuum vessel



Conceptual design of a cavity-pair cryomodule

ELBE/ALICE ERL Cryomodule

P. McIntosh, STFC Daresbury Laboratory





Original ELBE/ALICE Cryomodule 3D Drawings provided by FZD Rossendorf




Heavy Ions: TRIUMF ISAC-II

R. Laxdal, TRIUMF

- Low- β drift tube-loaded quarter wave cavities
- Common beam & insulating vacuum spaces



Heavy Ions: ATLAS




- $\beta=0.15$ DTL QWR
- Separated beam & insul. vac.



JLab SPX Cryomodule Concept (1)


J. Henry, JLab

- Based on CEBAF/SNS/12GeV Upgrade Evolution
- Shown with internal HOM loads




JLab SPX Cryomodule Concept (2)

J. Henry, JLab



Cornell ERL Injector Cryomodule (1): Cold Mass

M. Liepe, Cornell





- | | | | |
|------------------------------|-------------------------------------|-----------------------------|-----------------------------|
| ▪ Number of 2-cell cavities | 5 | ▪ Number of HOM loads | 6 |
| ▪ Acceleration per cavity | 1 – 3 MeV | ▪ Couplers per cavity | 2 |
| ▪ Accelerating gradient | 4.3 – 13.0 MV/m | ▪ RF power per cavity | 120 kW |
| ▪ R/Q (linac definition) | 222 Ohm | ▪ Amplitude/phase stability | $10^{-3} / 0.1^\circ$ (rms) |
| ▪ Qext | $4.6 \times 10^4 - 4.1 \times 10^5$ | ▪ ICM length | 5 m |
| ▪ Total 2K / 5K / 80K loads: | 30W / 60W / 700W | | |

Cornell ERL Injector Cryomodule (2): TTF Evolution

M. Liepe, Cornell


- Necessary changes compared to a TTF cryomodule:

- Increased diameter of 2K He pipes for high dynamic CW cavity loads
- Direct gas cooling of chosen 5K and 80K intercept points
- No 5K shield, only a 5K cooling manifold
- HOM absorbers between cavities
- New end-cap and feed-cap concept with reduced length




Cornell ERL Injector Cryomodule (3): CM Support

M. Liepe, Cornell



- Precision fixed cavity support surfaces between the beamline components and the HGRP
⇒ easy “self” alignment
- Cavity-subunits can be fine-aligned while cavities are at 2K (if required)




Cornell ERL Injector Cryomodule (4): Alignment

M. Liepe, Cornell

- Injector cryomodule cool-down to 4.2K in 2.5 days to minimize thermal stresses (<10 K/hour)
- Shift of cold mass (from Wire Position Monitor)
 - Expected: $dx = 0.38$ mm
 $dy = 0.94$ mm
 - Observed: $dx = 0.58$ mm
 $dy = 0.81$ mm

Cavity string is aligned to ± 0.2 mm after cool-down!




Cornell ERL Injector Cryomodule (5): Maintenance

M. Liepe, Cornell



3 weeks later




“module
in boxes”

- Injector module was disassembled during the last 3 weeks to
 - Re-process SRF cavities → improve Q_0
 - Fix absorber charging problem




Refrigeration (1)




Refrigeration (2)

- Pressure stability
- Vibration
- Off-design operation
- System margin
- Upgradeability
- Safety
- Reliability
- Efficiency
- Cost/delivery
- Similar systems




Refrigeration (3)

- Refrigeration @4.3K:
 - $COP_{INV} = 70 \text{ W/W}$
 - Carnot efficiency = 30%
 - Input power required = **230 W per watt at 4.3K**
- Refrigeration @2K:
 - $COP_{INV} = 150 \text{ W/W}$
 - Carnot efficiency = 18%
 - Input power required = **830 W per watt at 2K**




Schneider, Kneisel, Rode, "Gradient Optimization for SC CW Accelerators," PAC2003



ELBE Cryoplant FZ-Rossendorf

- Cryoplant hall: 17m x 10m
- 220W @ 1.8K + 200W @ 80K,
upgradeable to 380W with more
comp & LN2 precooling
- 417kW at full load (220W)



Cryoplant Costs

- Requirements are calculated using data from T. Smith, 03MAY10:
 - 312W for Q=1E9
 - 200W for Q=3E9
 - 161W for Q=1E10
 - 152W for Q=2E10
 - Same Qs, but ½ voltage
- Equivalent load includes **300W** for 5-8K intercepts and distribution sys. losses and **200W** equivalent for 40-80K shield load. This extra load is a fixed value and assumed to be independent of the 2K load.
- For cryoplants of this type, 1.8K operation adds 33% to plant size compared to 2.0K operation.

Load [W] @ operating temp	Equivalent load @ 4.5K [W]	Cost scaled from FNAL* [M\$]	Compressor power for 2.0K operation [kW]
270 (FNAL reference)	1230	8.0	295
312 (4MV @ Q=1E9)	1242	8.1	298
200 (4MV @ Q=3E9)	940	6.6	226
160.8 (4MV @ Q=1E10)	834	6.1	200
152.4 (4MV @ Q=2E10)	811	6.0	195
156 (2MV @ Q=1E9)	821	6.0	197
100 (2MV @ Q=3E9)	670	5.2	161
80.4 (2MV @ Q=1E10)	617	4.9	148
76.2 (2MV @ Q=2E10)	606	4.9	145

*Fermilab is buying a new cryoplant for ILC string tests. Design capacity is 270W@2K + 300W@5-8K + 4500W@40-80K (= 1230W equivalent at 4.5K). Costs scale with the 0.7 power of plant capacity (per Byrns & Green, "An update on estimating the cost of cryogenic refrigeration," 1998).