

---

# **Status of the ALS RF Systems**

**December 3, 2014**

**RF Group Leader: Slawomir Kwiatkowski  
Ken Baptiste, Qiang Du  
Max Vinco, Jim Julian (ret)**



# Scope

---


- ALS's RF Systems
  - Injection System
    - Electron Gun (125 MHz)
    - GTL Sub-Harmonic Bunchers (125 MHz & 500 MHz)
    - S-Band Linac (2.998GHz)
      - S-Band Buncher
      - S-Band Accelerating Sections
    - Booster RF System (500 MHz)
  - Storage Ring
    - Storage Ring RF System (500 MHz)
- 3<sup>rd</sup> Harmonic Cavities, passive (1.5 GHz)
- ALS RF Teststand
  - 66kW 500MHz Teststand
  - Titanium-Nitride Window Coating System




# Additional Scope

---


- SRRF Reliability History
- Things that didn't go quite right...
  - 12.5uF, 66kV Cap developed internal shorts
  - 4 1/16" Coax line fails




# ALS's RF Systems



# Injection System – Electron Gun & Linac



# E. Gun Electronics Equip Rack & Block Diagram




LINAC GUN ELECTRONICS SYSTEM

## Block Diagram

E. Gun Rack (LI01)

# E. Gun Pulse Train Generation




# Electron Gun Hot Deck, Gun Body, Cathode



**Hot Deck**



**Cathode life  
~4 years**




**Gun  
Body**

**Cathode  
Eimac YU-171**






# 125MHz & 500MHz Sub-Harmonic Bunchers (GTL SHB1 & SHB2)




125MHz – Eimac CV-2222  
500MHz – Eimac CV-2404




Eimac 3CPX800A7 (triode)  
Gain = 15dB  
Up to 6kW Pulse  
Tube Lifetime 10-12 years


# Photos of (GTL)




# Gun thru 3GHz LINAC RF System




# LINAC Modulators & Klystron




**Thales TV-2002: 24MW, 2us**  
**Lifetime: Mod #1: 17, 8+ yrs**  
**Mod #2: 9, 14, 1, 1+ yrs**




**Maintenance Items:**  
**HV Caps**  
**HVPS & Cable**



# LINAC




# Booster RF System



# Booster Ring RF System Parameters for 1.9 GeV


|                                      | <b>Present</b> |
|--------------------------------------|----------------|
| <b>Beam current (mA)</b>             | <b>4</b>       |
| <b>Dipoles Radiation (kW)</b>        | <b>&lt;5</b>   |
| <b>Cavity Dissipation (kW)</b>       | <b>43</b>      |
| <b>W.G. &amp; other losses (kW)</b>  | <b>6</b>       |
| <b>Total RF Power Reqr'd (kW)</b>    | <b>54</b>      |
| <b>Total RF Power Installed (kW)</b> | <b>80</b>      |

# BRF System Block Diagram





# BRF Transmission Line Sketch



Ratings:  
6 1/8" Coax: 80 kW Avg.

# BRF HPA/XMTR

## AI, Acrodyne Industries

(commercial broadcast transmitter, modified)



## CPI, Communications & Power Industries

(commercial broadcast IOT, K2 series, 80kW)



**Gain >23 dB**

**Eff. >65 %**


**$E_B <36$  kV**

**IOT #1: 18.1k hrs**

**IOT #2: +35k hrs**



# BRF HVPS (High Voltage RF Pad, outside Bldg.6)



# BRF Wave Guide Switch & HPA Test Load




Advanced Light Source



# BRF Circulator & Reject Load



# BRF Cavity




# SRRF Cavity






Advanced Light Source

# SR RF System




# Storage Ring RF System Parameters for 1.9 GeV

|                                        | Present |         |                                                                                       | Future  |         |
|----------------------------------------|---------|---------|---------------------------------------------------------------------------------------|---------|---------|
| Beam current (mA)                      | 500     |         |                                                                                       | 500     |         |
| Number of Insertion Devices            | 11      |         |    | 13      |         |
| Gap Positions                          | Nom     | Min     |                                                                                       | Nom     | Min     |
| Dipoles Radiation (kW)                 | 142     | 142     |                                                                                       | 142     | 142     |
| Insertion Device Radiation (kW)        | 25      | 46      |    | 46      | 55      |
| Power Loss for 3 <sup>rd</sup> HC (kW) | 6       | 9       |                                                                                       | 9       | 9       |
| Cavity Dissipation (x2) (kW)           | 43      | 43/50   |                                                                                       | 43/50   | 43/53   |
| W.G. & other losses (kW)               | 7       | 10/8    |                                                                                       | 10/9    | 12/9    |
| Total RF Power Reqr'd (kW)             | 266     | 293/305 |  | 293/305 | 304/322 |
| Total RF Power Installed (kW)          | 300     | 300     |                                                                                       | ~360    | ~360    |
| Cav/Window Power Limit (kW)            | 330     |         |                                                                                       | 330     |         |






# Original SR RF System Block Diagram




# Original SR RF HVPS




ALS SR KLYSTRON HV POWER SUPPLY SYSTEM  
(OUTDOOR UNIT)



# Original SR RF HVPS






# Original SR RF HVPS Filter & Crowbar System



NOTE: PLEASE REFER TO FILE DRAWINGS FOR DETAIL. CIRCUIT INFORMATION

SIMPLIFIED CIRCUIT DIAGRAM FOR THE ALS SR KLYSTRON AMPLIFIER

# Original SR RF Klystron & HVPS Filter/Crowbar Cabinet



125,000 HV hrs

Consuming 1 Tetrode every 3 years

Consuming 1 Thyatron every 3 years

Very, Very difficult to work on Crowbar firing circuit

Many hundreds of false triggers/crowbars

Removed 2012, G37.8,  $\eta = 43\%$

0.6dB,  $\eta = 55\%$


Advanced Light Source




# **SRRF Upgrade Requirements)**

---

- **Replace Aging Single Klystron (19+ yrs in 2012)**
- **Modest Increase in Max RF Power for Beam Loading/Reliability**
- **Replace HVPS only to Increase DC Power**
- **Replace HVPS Crowbar/Filter with Dis-Connect SW/Filter**
- **Replace Analog LLRF with Digital (FPGA) based system, improve amplitude and phase stability**
- **Upgrade Controls, from ILC to PLC**
- **Increase Diagnostic Capabilities, add synchronous fault data acquisition**
- **Increase Accessibility and Maintainability**



# Phase I, Install New Site #2 (2011 & 2012 Shutdown)



**Seismic Base Construction & Cabinet Installation at New Site #2**

**Klystron Installation**



**Mod-Anode Cabinet**


**PLC Control Rack**

**Site #2 Completed  
Operating since Feb-2012**

# Phase IIA, Install New HVTR/PS (2013 Shutdown)


## HVTR/PS

- 50kV @ 16A
- 12-pulse rectifier with filter inductor
- Complete, Operating since Feb-2013







# Phase IIB: Replace Crowbar w/HV Dis-Con SW & PLC Controls, Install Klystron Site #1 (2014 Shutdown)



# HV Dis-Con SW Block Diagram



# Phase IIB Completed

Filter/Crowbar Cabinet Replaced w/HV Dis-Con SW, PLC Controls, Kly Site #1 Completed 6/2014



HV Dis-Con SW



Klystron Site #1

Filter Cabinet and PLC Controls




# Phase IIB Completed


## PLC Controls



## HV Dis-Con Switch Performance




40 AWG  
Wire Test  
@ 50kV



40 AWG  
Wire Test  
@ 40kV



# Phase III, Replace LLRF & Upgrade Wave Guide System (2015 Shutdown)



## Operating Options:


Kly #1 to Cavity 1 (up to 180kW)

Kly #1 to both Cavities (300 kW)

Kly #2 to Cavity 2 (up to 180kW)


Kly #2 to both Cavities (300 kW)

Either Kly into Full Pwr Testload (300 kW)



**Two Digital LLRF Systems.**  
**RF Signal Diagnostics.**  
**MRF Timing System Clients**

# 3<sup>rd</sup> Harmonic (Landau) Cavities System



# 3<sup>rd</sup> Harmonic (Landau) Cavities System






Table 1: Harmonic cavity system parameters

|                      |         |
|----------------------|---------|
| Frequency            | 1.5 GHz |
| total voltage        | 500 kV  |
| bore diameter        | 5 cm    |
| cavity R/Q*          | 80.4    |
| calc. Q              | 27677   |
| calc. R <sub>s</sub> | 2.23 MΩ |
| R <sub>s</sub> x 70% | 1.56 MΩ |
| number of cells      | 4       |
| power per cell       | 5.01 kW |


$$*R = V^2/2P$$

# 3<sup>rd</sup> Harmonic (Landau) Cavities System







# Bldg. 27 RF Cavity Teststand, RF Window Processing



Split WR1800 Waveguide to Cavity Transition


## Current Design:

- 2 in SRRF operating at 43kW CW, 3 fully tested spares
- Manufactured by EEV, Marconi, now E2V
- TiN coating & test to 66KW CW at LBNL






Iris Flange Profile

$\beta$ : up to 3.2




# Bldg. 27 RF Cavity Teststand, Titanium-Nitride Coating



Coating thickness determined by Rutherford Back Scattering (RBS) performed on site at LBNL.

This sample measured 15 angstroms. Our target range is 10 – 20 angstroms.


# Bldg. 27 RF Cavity Teststand, Power Test/Condition Window



## B27 Cavity Teststand, 66kW @ 500MHz

- Identical cavity to Booster and Storage Ring

MC1 Power Test & Conditioning Cycle




- Power Conditioned in 24 Hrs over a 4 day period.
- 21 Rev Pwr Trips
- 5 Vac Trips
- Window Temp ran  $< 80^{\circ}\text{C}$


# SRRF Reliability

Percentage of Scheduled Beam Time Lost to SRRF & Non-Latching Faults by Fiscal Year

# of Faults/Yr




Goal for SRRF system based on 5000 hours of User Beam time: 0.3%




# SRRF Reliability

---

**SRRF Faults, MTBF (in hours): Mean time between faults, FY2004 - FY2013**




**Goal for SRRF system based on 5000 hours of User Beam time: 500 hrs**



# SRRF Reliability



SRRF Faults, MTTR (in minutes): Mean time to recovery, FY2004 - FY2013



Goal for SRRF system based on 5000 hours of User Beam time: 1.5 hrs





# Filter Cap Failure




# Advanced Photo-electron Experiment (APeX)

## 4 1/16" Coax Line Failed




**Main Overheated area**






# Advanced Photo-electron Experiment (APeX)

## 4 1/16" Coax Line Failed



$$\lambda_{RF}/4 \sim 15.9''$$



**Missing from measurements, additional ~5" for length of coupling loop**




**This hole is at a current node. The copper is melting here not arcing.**

**The internal conductor**

**This hole would then be at 27" + 5" = 32",  $\sim \lambda_{RF}/2$**

# Advanced Photo-electron Experiment (APeX)

## 4 1/16" Coax Line Failed



**EHT (Enhanced Heat Transfer coax line) rating from company:**

De-rating for 0 PSIG in line = 0.885

Average Power Rating = 89 kW derated to 78 kW

Peak Voltage Rating = 13 kV

Peak Power Rating = 3,685 kW ( $P_{pk} = V_{pk}^2/Z_0$ ). Not specified for how long.

**APEX max operation conditions:**

Power per coax line = 60 kW CW max (50 kW nominal).

Peak Voltage in line =  $1.414 \cdot \sqrt{P_{avg} \cdot Z_0} = 1.414 \cdot \sqrt{(60000 \cdot 50)} = 2.45 \text{ kV}$

Peak Power in line =  $V_{pk}^2/Z_0 = 2449^2 / 50 = 120 \text{ kW}$

Peak Power in line from standing wave:  $V_{pk} = 4.9 \text{ kV}$ ,  $P_{pk} = 480 \text{ kW}$



Facing parts

**The RF power remained ON for > 4 minutes in this condition due to improperly configured intrlks and a lack of synchronization when in pulse mode. Many watt-seconds were delivered during this time.**

**These arc marks are at a voltage maxima. There is no sign of overheating due to high currents. This arcing being ~3" from window would then be at  $19'' - \sim 3'' = 16''$ ,  $\sim \lambda_{RF}/4$**

