

# Undulator Manufacturing for the European XFEL



Suren Karabekyan

On behalf of Undulator Systems Group (WP71)

S. Abeghyan, M. Bagha-Shanjani, U. Englisch, F. Preisskorn, F. Wolff-Fabris, P. Li, Y. Li, J. Pflüger, T. Wei, M. Wünschel, M. Yakopov

# Overview

- European XFEL facility overview
  - Undulator system
  
- Undulator Segments
  - Serial Production of Undulator Segments:
    - External Production in Industry
    - XFEL.EU – WP71 Part
  - Representative Results
  
- Intersection Components
  
- Controls
  
- Undulator Systems
  - Installation
  - Commissioning
  - Maintenance

# Facility overview

## Schenefeld



- Experiment hall
- Laboratories
- Offices

## Osdorfer Born




- Electron beam to photon beamlines
- Undulator systems begin

## DESY-





- Electron source
- Linear accelerator begins



# Undulator Systems

## Photon Energy Range

	SASE1/2	SASE3
$\lambda_u$ [mm]	40	68
Operational Gap Range [mm]	10-20	10-25
K-Range	3.9-1.65	9.3-4
Radiation Wavelength Range [nm]		
@ 17.5 GeV	0.147-0.040	1.22-0.27
@ 14.0 GeV	0.230-0.063	1.90-0.42
@ 12.0 GeV	0.310-0.0828	2.44-0.621
@ 8.5 GeV	0.625-0.171	5.17-1.15
Number of Segments	35	21
System Length [m]	213.5	128.1



## Accelerator Layout

## SASE 1-3 : Undulator Systems

High repetition rate: < 27000 pulses/ sec

# Production Cycle

## External Production in Industry and XFEL.EU – WP71 Part

- Synergistic R&D together with DESY until 2008

- Industry Involvement

- Mechanical Support System : 2 Suppliers

- Magnetic Structure



- Local Motion Control



- Work done @ XFEL.EU

- Mechanics + Magnetics Integration @ XFEL.EU



- Commissioning @XFEL.EU

- Magnetic Measurement & Tuning

- Document Management System



# Serial Production of Undulator Segments: External Production in Industry

## Mechanical Support Systems



NORTEMECANICA, S.A.



July 2012



Dec 2012



Dec 2012

## Magnetic Structures



Nov 2012

## Local Control Systems



Nov 2012

# Production at European XFEL in Hall 5

New Undulator Segments

3 climatized Magnetic Labs

Assembly Area for  
Magnetic Structures

Segments waiting for  
Magnetic  
Measurements



Measured and tuned  
Segments

Incoming Magnetic  
Structures from VAC

Steps @ XFEL.EU:


- Mounting of magnetic structures
- Local Control System Commissioning
- Magnetic Measurements & Tuning
- Documentation, Preparation for Installation

Schedule:


- Total Time  $\approx$  2 Years (starting Oct/12)
- Scheduled End: Oct / End 2014
- $\rightarrow$  3 Magnetic Labs needed running in parallel
- 3 Weeks/Undulator

**Hall 5 was rapidly filled up. Assembled and tuned undulators were stored in a hall, outside of DESY premises .**

# Magnetic Measurements: Field Error Correction by Pole Height and Tilt Adjustment



- Adjustment Range:
- Pole Height :  $\pm 0.3\text{mm}$
- Pole Tilt :  $\pm 4\text{mrad}$









- Bipolar Field Corrections
- No Shims are used
- All errors are tuned by moving Poles



# Undulators: Representative Magnetic Results: U40-X046

XFEL Specs	U40	U68
Operational Gap Range [mm]	10-20	10-25
$B_0$ @ 10mm Gap [T]	1.14	1.66
K @ 10mm Gap	3.9	9.0
RMS $I_{2Y}$ [Tmm <sup>2</sup> ]	< 100	< 210
RMS $I_{2Z}$ [Tmm <sup>2</sup> ]	< 100	< 100
Phase Jitter [°]	≤ 8	≤ 8



# Re-Measurement Campaign


## Reasons:

1. 60% of the Undulator Segments were stored outside up to 2 ½ years with no temperature control (8-30° C)  
 Check prior to installation requested!
2. Improve accuracy of Hall Probe measurements and transferability between the labs to  $\Delta K/K = 2 \times 10^{-4}$  using new high stability, low drift, low noise probes (SENIS H3A-0YJ02F-B02T0K5K)
3. Apply exactly the same specs and procedures to all segments.
4. Precision Air Coil settings for Entrance/Exit Kicks using the Long Moving Wire Method rather than Hall Probes.

## Results:

- Only minor changes observed (entrance/exit kicks)
- Phase Jitter, straightness unchanged
- Probe data are much more stable


$\Delta K/K$ -Measurements on Reference Undulator U40-X057  
 in Hutches 1-3




U. Englisch, 19.10.2016

**Message: Accuracy Limit,  $\Delta K/K \leq \pm 2.0 \times 10^{-4}$  during the whole re-measurement campaign  
 Fall 2014 – September 2016**


# Measurement of Entrance and Exit Kick using the Moving Wire



Results on U40-X001, X042, X057




Paralell "P"



$$I1_B = \frac{\Delta\phi_P}{N \Delta y, z};$$

Anti-Paralell "A"




$$I2_B = \frac{L/2}{N \Delta y, z} \{\Delta\phi_P - \Delta\phi_{AP}\}$$

D. Zangrando, R.P. Walker, Nucl. Instr. And Meth, A376 (1996), 275

Accuracy:  $\Delta I1 \leq \pm 5 \text{ G.cm}$ ;  $\Delta I2 \leq \pm 2000 \text{ G.cm}^2$



# Intersection

- Undulator System Group (WP71) is responsible for the following components: Quadrupole Mover, Phase Shifter, Air coils, Support basies, Intersection Control Racks,
- 9 companies were producing the intersection components for WP71



# Phase Shifters with very low 1st Field Integral errors: Representative Results

- Period length: 55mm
- Gap range: 10.5 to  $\approx >100$ mm
- Max. Phase Integral @ gap 10.5mm :  $\geq 23400 \text{ T}^2\text{mm}^3$
- **1st Hor/Ver Field Integral Tolerance:  $\pm 0.004 \text{ Tmm}$**
- **Dynamic Operation without retuning!**
- 2nd Hor/Ver Field Integral Tolerance:  $\pm 67 \text{ Tmm}^2$
- Min. Gap precision for 5° SASE1/2  $\pm 15\mu\text{m}$



Y. Li, J. Pflueger, Phys. Rev. STAB 18, 030703 (2015)


■ 1st Field Integrals: Important for independent operation, no corrections required (31 Phase Shifters, Huihua Lu, Lingling Gong, Yajun Sun, IHEP)

$$\Delta\varphi = \frac{2\pi}{\lambda_0(1+0.5K^2)} \left(\frac{e}{mc}\right)^2 PI = \frac{2\pi}{\lambda_R 2\gamma^2} \left(\frac{e}{mc}\right)^2 PI$$




## Intersection

- Factory acceptance tests (FAT) have been requested: Documentation stored in the EDMS
- All necessary hardware for the FAT have been provided by European XFEL
- After delivery of all components to European XFEL, site acceptance tests were arranged.
- If any of the components didn't match the specifications, this component was sent back to the manufacturer
- Our experience has demonstrated that after the SAT only 1% of the delivered QMs and PSs needed to be returned.
- Approximately the same failure rate has been observed for ICRs
- No returns for Air coils and Support bases




# Documentation Database in EDMS

- Drawings
- Tender Material
- Procurement
- Access
- Magnetic data of all Undulator Segments, Phase Shifters, Air Coils



# Undulator Controls System




- The undulator control system is based on industrial components produced by Beckhoff company and a PLC implemented in the TwinCAT system.

LCN in SASE1


# Undulator Local Controls System: Commissioning in the Labs

- Magnetic measurements
  - ▶ Alignment of the undulator relative to the magnetic measurement bench
  - ▶ Magnetic measurements and field fine tuning
  - ▶ Final measurements and documentation of magnetic properties of undulator
  
- Control system commissioning
  - ▶ Installation and adjustment of the linear encoders to reach an accuracy of  $\pm 1\mu\text{m}$ .
  - ▶ Adjustment of the tilt angles of the undulator girders to better than  $\pm 150\mu\text{rad}$
  - ▶ Evaluation of the feedforward correction coefficients for the rotary encoders
  - ▶ Calibration of the temperature sensors



Without automation of the control system commissioning 3 Weeks/Undulator production speed will be impossible

## Evaluation of the feedforward correction coefficients



- Strong magnetic forces cause an elastic deformation of the undulator support frame at small gaps
- Thus cause deviations between the linear and the rotary encoder readings
- The rotary encoder reading needs to be corrected for deformation effects
- Since deformation is elastic, a feedforward correction can be applied
- The Gauss–Newton least-squares algorithm was used to fit the nonlinear function  $f(\mathbf{c}, x)$  with parameters  $\mathbf{c} = (c_1, c_2, \dots, c_n)$  to the measured data  $(x_i, y_i) (i = 1, 2, \dots, m)$ .
- A fitting function  $f(\mathbf{c}, x) = c_1 + c_2 * e^{\frac{(x-x_0)}{c_3}}$  was selected and is used in the program






# Software for commissioning of an undulator system


## Image Deployment Automation Components

- A specific feature of undulator systems for free-electron lasers is the large number of repeating elements.
- The software running on each LCN must be identical, although each cell component has its individual settings
- The other aspect is the need to have possibilities to update the version of the TwinCAT software as well as specific firmware.
- These arguments lead to the decision to develop software which will automate this process




# Image Deployment Automation: Components

## Central Control Node



## Local Control Node



# Image Deployment Automation

## Update

Image Manager --- version: 2.0.2.175

Cells | Settings

Cell	IP Address	MAC Address	Version	Status	Ping	Operation	Last Status
<input type="checkbox"/> 1	10.10.1.1	N/A			✗		No Action
<input type="checkbox"/> 2	10.10.1.2	N/A			✗		No Action
<input type="checkbox"/> 3	10.10.1.3	000105128202		✓	✓	Done, rebooting...	29-Sep-15 3:13:33 PM
<input type="checkbox"/> 4	10.10.1.4	0001050FE396		✓	✗		07-Oct-15 11:18:32 AM
<input type="checkbox"/> 5	10.10.1.5	000105116466		✓	✗		07-Oct-15 10:25:30 AM
<input checked="" type="checkbox"/> 6	10.10.1.6	0001050DEC44		✓	✗		07-Oct-15 10:27:16 AM
<input type="checkbox"/> 7	10.10.1.7	N/A		✓	✗		23-Sep-15 5:09:26 PM
<input type="checkbox"/> 8	10.10.1.8	N/A			✗		No Action
<input type="checkbox"/> 9	10.10.1.9	N/A			✗		No Action
<input type="checkbox"/> 10	10.10.1.10	N/A			✗		No Action
<input type="checkbox"/> 11	10.10.1.11	N/A			✗		No Action
<input type="checkbox"/> 12	10.10.1.12	N/A			✗		No Action
<input type="checkbox"/> 13	10.10.1.13	N/A			✗		No Action
<input type="checkbox"/> 14	10.10.1.14	N/A			✗		No Action
<input type="checkbox"/> 15	10.10.1.15	N/A			✗		No Action
<input type="checkbox"/> 16	10.10.1.16	N/A			✗		No Action
<input type="checkbox"/> 17	10.10.1.17	N/A			✗		No Action
<input type="checkbox"/> 18	10.10.1.18	N/A			✗		No Action
<input type="checkbox"/> 19	10.10.1.19	N/A			✗		No Action
<input type="checkbox"/> 20	10.10.1.20	0001050DEC54		✓	✗		06-Oct-15 9:31:49 PM
<input type="checkbox"/> 21	10.10.1.21	N/A			✗		No Action
<input type="checkbox"/> 22	10.10.1.22	N/A			✗		No Action
<input type="checkbox"/> 23	10.10.1.23	N/A			✗		No Action
<input type="checkbox"/> 24	10.10.1.24	N/A			✗		No Action
<input type="checkbox"/> 25	10.10.1.25	N/A			✗		No Action
<input type="checkbox"/> 26	10.10.1.26	N/A			✗		No Action
<input type="checkbox"/> 27	10.10.1.27	N/A			✗		No Action
<input type="checkbox"/> 28	10.10.1.28	N/A			✗		No Action
<input type="checkbox"/> 29	10.10.1.29	N/A			✗		No Action
<input type="checkbox"/> 30	10.10.1.30	N/A			✗		No Action
<input type="checkbox"/> 31	10.10.1.31	N/A			✗		No Action
<input type="checkbox"/> 32	10.10.1.32	N/A			✗		No Action

Operations

Update Params | Update Image | Refresh Versions | Refresh Status | Refresh Ping | Make Master | Filter

Undula  
System  
Databa  
ORAC

# Image Deployment Automation

Up

Image Manager --- version: 2.0.2.175

Cells Settings

Cell	IP Address	MAC Address	Version	Status	Ping	Operation	Last Status
<input type="checkbox"/> 1	10.10.1.1	N/A			✗		No Action
<input type="checkbox"/> 2	10.10.1.2	N/A			✗		No Action
<input type="checkbox"/> 3	10.10.1.3	000105128202		✓	✓	Done, rebooting...	29-Sep-15 3:13:33 PM
<input type="checkbox"/> 4	10.10.1.4	0001050FE396		✓	✗		07-Oct-15 11:18:32 AM
<input type="checkbox"/> 5	10.10.1.5	000105116466		✓	✗		07-Oct-15 10:25:30 AM
<input checked="" type="checkbox"/> 6	10.10.1.6	0001050DEC44		✓	✗		07-Oct-15 10:27:16 AM
<input type="checkbox"/> 7	10.10.1.7	N/A			✗		23-Sep-15 5:09:26 PM
<input type="checkbox"/> 8	10.10.1.8	N/A			✗		No Action
<input type="checkbox"/> 9	10.10.1.9	N/A			✗		No Action
<input type="checkbox"/> 10	10.10.1.10	N/A			✗		No Action
<input type="checkbox"/> 11	10.10.1.11	N/A			✗		No Action
<input type="checkbox"/> 12	10.10.1.12	N/A			✗		No Action
<input type="checkbox"/> 13	10.10.1.13	N/A			✗		No Action
<input type="checkbox"/> 14	10.10.1.14	N/A			✗		No Action
<input type="checkbox"/> 15	10.10.1.15	N/A			✗		No Action
<input type="checkbox"/> 16	10.10.1.16	N/A			✗		No Action
<input type="checkbox"/> 17	10.10.1.17	N/A			✗		No Action
<input type="checkbox"/> 18	10.10.1.18	N/A			✗		No Action
<input type="checkbox"/> 19	10.10.1.19	N/A			✗		No Action
<input type="checkbox"/> 20	10.10.1.20	0001050DEC54		✓	✗		06-Oct-15 9:31:49 PM
<input type="checkbox"/> 21	10.10.1.21	N/A			✗		No Action
<input type="checkbox"/> 22	10.10.1.22	N/A			✗		No Action
<input type="checkbox"/> 23	10.10.1.23	N/A			✗		No Action
<input type="checkbox"/> 24	10.10.1.24	N/A			✗		No Action
<input type="checkbox"/> 25	10.10.1.25	N/A			✗		No Action
<input type="checkbox"/> 26	10.10.1.26	N/A			✗		No Action
<input type="checkbox"/> 27	10.10.1.27	N/A			✗		No Action
<input type="checkbox"/> 28	10.10.1.28	N/A			✗		No Action
<input type="checkbox"/> 29	10.10.1.29	N/A			✗		No Action
<input type="checkbox"/> 30	10.10.1.30	N/A			✗		No Action
<input type="checkbox"/> 31	10.10.1.31	N/A			✗		No Action
<input type="checkbox"/> 32	10.10.1.32	N/A			✗		No Action

Operations

Update Params Update Image Refresh Versions Refresh Status Refresh Ping Make Master Filter


ode




# Undulator System Tester

- The next step after putting the undulator system into operation is the commissioning of all control components that belong to it
- This task could be time consuming because several hundred values per system must be examined.
- This was a motivation to create a supervisory control and data acquisition (SCADA) program.
- This program is running on the CCN and is sending commands to the LCNs.
- After the execution of the commands, the program receives a feedback value.
- If the value is inside of an expected range, then the test is accepted; otherwise the test is marked as not successful.

# Undulator System Tester




# Temperature Distribution in SASE1 System measured Sep.3 – Oct. 3 (Holidays)




**SASE1 PKG**



**Temperature along SASE 1**






**Time Dependence at Cells 3, 19, 37**



# Hardware Management in Tunnel: Reference Gap Measurement Device

## ■ Gap measurement principal

- ▶ 4 Micro-Epsilon calibrated capacitive sensors
- ▶ @ constant gap and thickness of vacuum chamber  $\Sigma$  is constant
- ▶ Holder fixed using magnetic force
- ▶ Sub micrometer measurements reproducibility
- ▶ Measurements are independent from the temperature of the holder and quasi-independent from the temperature of the sensors
- ▶ With non magnetic gauge can be used without vacuum chamber



# Undulator Systems Instalation in the Tunnel

## Status of SASE1 & SASE3 May 2017


### Status

- Undulator Hardware installed: Quadrupoles, Quadrupole Movers, Magnet Power, Cooling Water, Phase Shifters,
- Undulator Control System commissioned, operational
- Undulator System aligned with SLRS
- Interlocks installed
- Air Conditioning System installed & commissioned
- **SASE1 System “Ready for Beam“ since March, 2017**
- **SASE3 System “Ready for Beam“ since April 14, 2017**

Thank you for your  
attention!



Enclosure closed




Enclosures opened for  
SLRS alignment





# Adjustment of the linear encoders



- The installation of a profiled linear guideway has to be validated in order to ensure the requirements of the gap measurement accuracy



LAN



# Adjustment of the linear encoders

- The program sequentially changes the gap and reads the value of linear encoders and reference gauges

**Undulator Hysteresis Measurement**

Serial Numbers for Undulator  
 Undulator SN: X092-1001 | Left Encoder SN: 32496757N | Right Encoder SN: 32496755N | Left Gauge SN: 36524228D | Right Gauge SN: 36524231D


Tolerances  
 Hysteresis(mm) ±: 0.002 | Deviation(mm) ±: 0.01

Measurement Values  
 SetGap(mm): 100 | ActualGap(mm): 99.99998  
 Left Encoder(mm): 100.05851 | Right Encoder(mm): 99.98089  
 Left Gauge(mm): 100.05862 | Right Gauge(mm): 99.98047  
 Left Deviation(mm): 0.00011 | Right Deviation(mm): -0.00042

Setting Parameters  
 1. Run-TimeSystem (PORT 801) |  2. Run-TimeSystem (PORT 811)  
 ND 287 IP Address: 169.254.1.2  
 Configuration File: C:\Commissioning(config\_long\_1mm.ucf)  
 Save File: C:\X092-1001\_2012.04.20\_15h54'09".txt


Buttons: Start, Stop, Graph, Final state

Information: PLC Version: 31 Revision: 0 Build: 26 The ID is: 10.0.1.92.1.1




SetGap	ActGap	LeftELC	RightELC	MTLeft	MTRight	DIFFL	DIFFR
100.0	100.00002	100.05805	99.98131	0.00000	0.00000	0.00000	0.00000
99.0	99.00002	99.05802	99.98020	1.00090	1.00087	0.00013	0.00018
98.0	98.00003	98.05781	97.98124	2.00297	1.99955	0.00027	0.00057
97.0	97.00002	97.05781	96.97846	3.00434	3.00205	0.00070	0.00084
96.0	96.00003	96.05518	95.97732	4.00318	4.00137	0.00069	0.00067
95.0	95.00003	95.05874	95.97848	5.00247	5.00136	0.00105	0.00058
94.0	94.00002	94.05787	93.97500	6.00020	6.00594	0.00098	0.00042
93.0	93.00003	93.05883	94.97190	7.00047	7.00046	0.00000	0.00000
92.0	92.00003	92.05999	92.97886	7.99773	8.00191	0.00133	0.00058
91.0	91.00002	91.05887	90.98081	8.99815	9.00020	0.00185	0.00018
90.0	90.00003	90.05935	89.98176	9.99856	9.99937	0.00144	0.00022
89.0	89.00003	89.05708	88.97930	11.00017	11.00138	0.00140	0.00068
88.0	88.00003	88.05107	87.98109	12.00465	12.00086	0.00133	0.00041
87.0	87.00002	87.05244	86.97927	13.00438	13.00118	0.00205	0.00070
86.0	86.00003	86.05423	85.97664	14.00063	14.00417	0.00219	0.00055
85.0	85.00002	85.05621	84.97712	15.00062	15.00407	0.00223	0.00017
84.0	84.00002	84.05877	83.97394	15.99795	16.00338	0.00223	0.00004
83.0	83.00003	83.05968	82.97677	16.99908	17.00040	0.00241	0.00018
82.0	82.00003	82.06091	81.98007	17.99516	18.00115	0.00298	0.00013
81.0	81.00002	81.06167	80.98036	18.99412	19.00110	0.00276	-0.00013
80.0	80.00002	80.05970	79.98209	19.99932	19.99980	0.00223	-0.00033
79.0	79.00003	79.05823	78.98189	20.99848	20.99982	0.00315	-0.00043
78.0	78.00003	78.05533	77.98091	22.00003	22.00112	0.00368	-0.00068

Measurement data for Undulator SN X092-1001




## Adjustment of the tilt angle of the girders





- Due to magnetic force between upper and lower magnet structures the undulator frame bends and the girder tilt angle changes as a function of the undulator gap typically by  $\pm 250 \mu\text{rad}$
- The magnet girders of an undulator have a rotational degree of freedom
- To minimize the influence on the magnetic field the girder tilt should be adjusted symmetrically around the vertical position



# Adjustment of the tilt angle of the girders



- WYLER's BlueLEVEL high precision electronic inclination measuring instruments are used to measure the angles on four machined reference surfaces of the girders
- The program runs on a separate PC



# Adjustment of the tilt angle of the girders

- The program sequentially changes the undulator gap value and reads the tilt angle of undulator girder.

The BlueSPIRIT interface displays the following parameters for undulator X044-K004:

- Undulator Serial NO.: X044-K004
- AMS: 10.0.1.2.1.1
- Configuration File: C:\Documents and Settings\LAB-NO ...
- Measurement Mode: Double Measurement
- Set Gap: 10.000, Real Gap: 9.996
- Blue Level Value: COM PORT NO. (COM2, COM4), POSITION (G, H), TILT ANGLE (-0.04, -0.015)

The graph shows the tilt angle (mm/m) as a function of the gap (mm) for girders E, F, G, and H. The x-axis ranges from 0 to 200 mm, and the y-axis ranges from -0.21 to 0.06 mm/m. Girders E and F show a sharp initial drop in tilt angle before leveling off near zero. Girders G and H show a more gradual decrease, leveling off at approximately -0.10 mm/m.

\_2013.01.28\_22h32'16".txt - Notepad

```

File Edit Format View Help
2013/01/28 22:51:55
SetGap      E          F          G          H
-----
200.0      -0.114000  0.099000  -0.082000  0.099000
150.0      -0.113000  0.100000  -0.075000  0.107000
100.0      -0.112000  0.102000  -0.070000  0.112000
 50.0      -0.113000  0.101000  -0.070000  0.112000
 40.0      -0.114000  0.100000  -0.070000  0.112000
 35.0      -0.115000  0.099000  -0.069000  0.113000
 30.0      -0.118000  0.096000  -0.065000  0.117000
 25.0      -0.126000  0.091000  -0.059000  0.121000
 22.0      -0.129000  0.086000  -0.049000  0.132000
 20.0      -0.136000  0.080000  -0.040000  0.140000
 19.0      -0.145000  0.072000  -0.026000  0.154000
 18.0      -0.150000  0.067000  -0.023000  0.157000
 17.0      -0.156000  0.062000  -0.015000  0.161000
 16.0      -0.164000  0.055000  -0.013000  0.163000
 15.0      -0.173000  0.047000  -0.024000  0.154000
 14.0      -0.183000  0.037000  -0.037000  0.141000
 13.0      -0.194000  0.027000  -0.046000  0.130000
 12.0      -0.208000  0.014000  -0.050000  0.126000
 11.0      -0.224000  0.000000  -0.045000  0.129000
 10.0      -0.247000  -0.019000  -0.037000  0.134000
    
```

Tilt Angle of Unulator SN X055 - K015Girder

The graph shows the tilt angle (mm/m) as a function of the gap (mm) for girders E, F, G, and H. The x-axis ranges from 0 to 200 mm, and the y-axis ranges from -0.10 to 0.35 mm/m. Girders E and F show a sharp initial drop in tilt angle before leveling off near zero. Girders G and H show a more gradual decrease, leveling off at approximately -0.05 mm/m.

2013/01/10 16:16:49

```

SetGap      E          F          G          H
-----
200.0      0.164000  0.091000  0.192000  0.168000
150.0      0.167000  0.092000  0.195000  0.169000
100.0      0.169000  0.093000  0.196000  0.170000
 50.0      0.167000  0.091000  0.193000  0.167000
 40.0      0.165000  0.089000  0.191000  0.165000
 35.0      0.163000  0.087000  0.189000  0.163000
 30.0      0.159000  0.084000  0.185000  0.158000
 25.0      0.152000  0.079000  0.178000  0.151000
 22.0      0.148000  0.077000  0.174000  0.148000
 20.0      0.138000  0.069000  0.165000  0.139000
    
```