

# APS-U Beam Stability Requirements and R&D in Sector 27



**Nick Sereno**

Diagnostics Group Leader  
Accelerator Systems Division/Diagnostics

APS-U Forum  
March 10, 2016

# Outline

- Beam Stability R&D Effort at APS
- General Requirements for Beam Positioning and Stability
- APS-U Beam Stability Requirements
- APS-U Beam Stability R&D Scope
- Beam Stability R&D in Sector 27
  - Mechanical Motion Sensing (MMS)
  - GRID XBPM comparison to existing photoemission XBPMs
  - GRID/MMS testing using existing feedback system
- Sector 27 tests of APS-U feedback controller prototype
  - Four bpm, four corrector testing (began testing in ring in February 2016)
  - Integrated testing (coming this fall)
- Summary

# APS Beam Stability R&D Effort

- All three APS divisions and FMS
- APS Project Office
- Outside Collaborators (National and International Labs)
- Beam Stability Working Group (G. Srajer chair)
  - Representatives from APS Divisions and Users
  - Discuss improvements to present storage ring beam stability and related items (steering automation, temperature stability etc.)
  - Discuss implications for future MBA upgrade

# General Requirements for Orbit Positioning and Stability for the MBA Ring

- Commissioning -
  - Obtain first turn trajectory, close the orbit, store and perform optics correction
- ID steering -
  - Put photon beam on user target within a fraction of the beam size
  - Recover the orbit within a fraction of the beam size at each ID after a shutdown
- Recover the orbit close to the magnetic centers of the multipoles
- Maintain a stable beam trajectory -
  - Long term drift  $> 100$  seconds to 7 days
  - Maintain AC beam motion to a fraction of the beam size
- Ultimately the definitions of beam drift and AC motion “noise” depend on the details of the user experiment...

# MBA Orbit Stability Requirements

## Minimum Expected Beam Size at the IDs

$\sigma_x$	$\sigma_{x'}$	$\sigma_y$	$\sigma_{y'}$
17 $\mu\text{m}$	2.6 $\mu\text{rad}$	4 $\mu\text{m}$	1.7 $\mu\text{rad}$

## Beam Stability Goals for the APS Upgrade


Plane	AC rms Motion (0.01-1000 Hz)	AC rms Motion (0.01-1000 Hz)	Long-term Drift (>100 s)	Long-term Drift (>100 s)
Horizontal	1.7 $\mu\text{m}$ rms (>6 $\mu\text{m}$ )	0.26 $\mu\text{rad}$ rms (>1.7 $\mu\text{rad}$ )	1 $\mu\text{m}$ rms (~10 $\mu\text{m}^*$ )	0.6 $\mu\text{rad}$ rms (~2.8 $\mu\text{rad}^*$ )
Vertical	0.4 $\mu\text{m}$ rms (>3 $\mu\text{m}$ )	0.17 $\mu\text{rad}$ rms (>0.85 $\mu\text{rad}$ )	1 $\mu\text{m}$ rms (~10 $\mu\text{m}^*$ )	0.5 $\mu\text{rad}$ rms (~2.8 $\mu\text{rad}^*$ )

( ) Present Storage Ring Performance  
\* Peak-to-Peak


# Beam Stability R&D Scope

- Achieving beam stability requirements for APS-U requires integration of many subsystems:
  - Commercial bpm diagnostics (both electron and photon)
  - Fast and slow corrector power supplies
  - Mechanical motion sensing of vacuum chamber motion
  - Main cavity and HHC (bunch lengthening) cavity rf systems, multibunch feedback systems
  - Real-Time Orbit feedback system – updates fast and slow correctors based on beam position information using a “unified” feedback algorithm
  - Good regulation of tunnel air and water temperature systems (Lester’s talk)
  - Comprehensive data acquisition system (DAQ) for diagnostics and all accelerator sub-systems (power supplies, rf, injection, injectors ...)
  - User beamline diagnostic systems
- The integrated system must meet challenging beam stability requirements
- I will discuss sector 27 R&D results and activities

# Beam Stability R&D In Sector 27 of the Storage Ring




# Mechanical Stability - 24 bunch, 2-minute Top-up






# Mechanical Stability - Impact With Orbit Feedback




- Performed various experiments using sector 27 diagnostics to quantify how mechanical motion impacts beam motion
- ID vacuum chamber can be moved vertically and held to sub-micron accuracy
- Vacuum chamber vertical position feedback holds vacuum chamber at a user selected mechanical position
  - Uses heater tape to heat or cool (stop heating) supports based on position setpoint
  - Cooling (turning off heater) is relatively slow due to diffusion of heat into the air

# Mechanical Stability - Impact With Orbit Feedback cont.




- Upstream ID BPM
- Downstream ID BPM

Nominal Trajectory



Downstream ID BPM Mechanical Steering




Downstream ID BPM Orbit Feedback Steering Back to Nominal


- Note only 1 degree increase in temperature results in 5  $\mu\text{m}$  VC support increase



# Mechanical Stability - Impact With Orbit Feedback cont.




# GRID XBPM Commissioning




# GRID XBPM Commissioning cont.

## Design: GRID-XBPM Assembly



# GRID XBPM Commissioning cont.





# GRID XBPM Commissioning cont.

Horizontal beam position

Data from User Operations Run 2015-02

Vertical beam position




- Long term performance of the GRID XBPM in sector 27



# Targets for Orbit-Feedback Performance Improvements

Open- vs closed-loop PSDs with present RTFB (x-plane)





# Orbit Feedback Performance Improvements


- Reduce long term drift -
  - Measure movement of BPMs using MMS system and correct after ring has “settled”
  - Move ID BPMs off the ID vacuum chamber to their own stable supports
  - Include GRID XBPMs in orbit feedback
  - Good drift performance from BPM electronics (measured in SR  $\sim 10$  nm over 5 days<sup>1</sup>)
- Reduce residual uncorrectable motion
  - Add more fast correctors (2 per sector per plane instead of 1)
  - Improved orbit correction feedback algorithm
- Widen correction bandwidth to 1 kHz (from present  $\sim 80$  Hz)
  - Fast corrector power supplies small signal bandwidth to 10 kHz
  - Laminated-core 8 pole fast corrector magnet under development at Brookhaven (need DC steering range too)
  - Use thin Inconel chamber to minimize attenuation and time delays for AC field components
  - Minimize latency through the entire system using:
    - Modern data links to feedback controllers (60x faster than present RTFB system)
    - Modern DSPs to process bpm data to corrector setpoints (2000x faster than RTFB)




# Initial Feedback Controller Testing in S27 (4x4 Test)

- Configured prototype feedback controller to use:
  - Four commercial bpm electronics (Instrumentation Technologies)
  - Existing fast bpm's in sectors 27 and 28
  - Existing DSP code from operations RTFB system
  - Update rate of 22.6 kHz or 15x present RTFB system and closed the loop
  - Performed initial frequency and step response tests

# Initial Feedback Controller Testing in S27 (4x4 Test)




# Initial Feedback Controller Testing in S27 (4x4 Test)



- Step response comparison between standard RTFB and 4x4 test prototype feedback controller

# Integrated Beam Stability R&D Testing in S27 (Fall 2016)




# Summary

- Beam stability R&D in sector 27 is well underway to address the challenging requirements for the MBA ring
  - Tested prototype mechanical motion sensing system in sector 27
  - Tested prototype GRID XBPM in sector 27
  - Testing prototype feedback controller now in sector 27, 28 (4x4 test)
  - Integrated testing in sectors 27 and 28 to commence Fall of this year
- Longer term possibilities:
  - Leverage R&D in sectors 27 and 28 and upgrade legacy feedback, bpm, Xbpm systems before upgrade

# Beam Stability R&D Team

- AES – Controls:
  - R. Farnsworth, F. Lenkszus, A. Pietryla, S. Shoaf, S. Veseli, S. Xu
- APS Upgrade Project:
  - N. Arnold, J. Carwardine, G. Decker
- ASD – Accelerator Operations and Physics
  - L. Emery, V. Sajaev, H. Shang, A. Xiao
- ASD – Diagnostics:
  - A. Brill, H. Bui, L. Erwin, R. Keane, B. Lill, N. Sereno, B. X. Yang
- ASD – Power Supplies:
  - B. Deriy, T. Fors, J. Wang
- ASD-RF:
  - T. Berenc, H. Ma
- APS Users:
- FMS:
  - M. Kirshenbaum, G. Kailus

# Extra Slide: Data Acquisition System for All Accelerator Subsystems




## Block diagram of the prototype DAQ system installed in the APS SR

- Prototype DAQ system can acquire SR LLRF and Reflective Memory data from the existing feedback system at 1.5 kHz
- Future DAQ system acquires timestamped data up to turn-by-turn (271 kHz) rates across all accelerator systems: BPMs, DSC, Power Supplies, RF, Injection ...etc.



# Extra Slide: APS - U Feedback Controller Modular Concept



## Extra Slide: Feedback System Key Parameters Comparison

Parameter	MBA RTFB	Datapool	RTFB
BPM Sample rate	271 kHz (turn-by-turn)	10 Hz	1.5 kHz
BPM Orbit Vector transfer rate	271 kHz (goal)	10 Hz	1.5 kHz
Fast Corrector PS setpoint rate	22 kHz	10 Hz	1.5 kHz
Processing hardware	FPGAs / DSPs	EPICS IOC	DSPs
Rf bpms	570 / plane	360 / plane	160 / plane
ID X-ray bpms	90 / plane	50 / plane	-
Fast correctors	160 / plane	-	38 / plane
Slow correctors	320 / plane	300 / plane	-
Fast corrector bandwidth	10 kHz	-	*700-800 Hz
Slow corrector bandwidth	~1 Hz	~1 Hz	-
Closed-loop bandwidth	DC to 1 kHz	DC - 1 Hz	1 Hz - 80 Hz

\* Power supply, magnet and vacuum chamber

- Present system consists of a slow (Datapool) and fast (RTFB) system (standard operations mode)
- A main goal of **MBA RTFB** is to unify slow and fast orbit correction into a single algorithm

