

APS SITE OPERATIONS CNM and LOM 437 Overview

June 30, 2004

Richard Janik
Conventional Facilities Manager







Construction Readiness Overview Advanced Photon Source



- Purpose is to create, characterize and understand the behavior of new functional materials on the nanoscale
- A two-story, 85,000 sq. ft. structure attached to the west side of the APS Experiment Hall
- Conventional Facilities budget: \$36M funded by the State of Illinois
- Schedule:
 - Approve Final Design
 - Start Construction
 - Accept Building

January, 2004


July, 2004

April, 2006

CNM Construction Task Organization Chart

Advanced Photon Source

Operations Division




Conventional Facilities

Advanced Photon Source


CNM Construction Area

- Main CNM construction site will be enclosed and gated
- Kearney Road to be closed during construction
- Construction staff to use existing parking area south of CNM site



CNM Building Program





Building Program

The CNM building has been programmed into four major functional areas. These areas are segregated by security access devices that will be controlled by personnel type, e.g., employee, user, visitor, support staff, etc. The areas are further developed by the scientific research themes being utilized with the MIE portion of this project.

X-ray Nanoprobe Beamline

LOM 437 Overview

- After completion of the CNM construction project, vibration-sensitive experiments will take place in the CNM building.
- Because of the proximity of LOM 437 to the CNM, it is necessary to install LOM 437 vibration-causing construction activities before they affect these experiments.
- Thus far, \$2.5M is available for Phase I, which includes site work, excavation, foundation and slab on grade.

Conventional Facilities



Operations Division

LOM 437

- 22,000 sq. ft. single-story laboratory / office building with second-floor mechanical mezzanine
- Located between CNM and LOM
 438 and attached to the northwest quadrant of the APS Experiment
 Hall
- Last of 8 LOMs envisioned for APS
- Provides office and lab work area for APS users operating experimental beamlines
- Scheduled for construction in the summer of FY05



LOM 437 Construction Strategy

Phased Project Implementation Approach

- Due to uncertain funding for LOM 437 (sources, amounts, and time frame), a phased approach will allow the APS to incrementally construct the final LOM as funding becomes available.
- Eight separate work packages will be put together.
- Each work package will be a separate procurement complete with scope of work, drawings and specs.
- Greater economy and faster completion could be achieved as more packages are combined together.

Conventional Facilities



LOM 437 Estimate

Proposal	Project Proposal	Total Bldg.
#	Packages	Cost (\$k)
P-0	Engineering Design	150
P-1	Work Inside Bldg.	220
	400/Exp. Hall	
P-2	Building Slab and U/G Work	850
P-3	Site Work	220
P-4	Prepurchase MEP Equipment	175
P-5	Prepurchase Proprietary	110
	Controls	
P-6	Structural Framing	850
P-7	Phase I Building Shell	2900
P-8	Phase II Building Completion	2700
	TOTAL	8175